

SPACE READINESS

For Contractors and Homeowners



SHOWERS

Every surface where glass will sit must be fully installed before we laser template. We capture measurements down to every 1/16", so precision matters.

- Tile and shower curb must be completely installed where the glass touches.



VANITIES

Backsplash, countertop, and electrical rough-ins must be installed or ready before we template.

- Outlets, lights, and switches should be roughed in or installed (not necessarily finished).
- Countertops and backsplashes must be in place or ready to go.
- Remove any plumbing fixtures that would block mirror installation—if we can't fit it in, we can't install it.